

May 12, 2022

NJSEA Meadowlands Fire House Roof Replacement

East Rutherford, New Jersey

Bid Due Date: May 19, 2022 @ 12:00PM

ADDENDUM #2

RFI Questions

1. **Question:** The asbestos report states the west side of the roof has 10% chrysotile asbestos in 8,000 sf of hot tar layer 1. The re-roofing area for this bid is approximately 6,200 sf, does this mean the whole re-roof area is asbestos or is the 8,000 sf in another area?
Response: Yes, the whole re-roof area of 6,200 sf as per the plans and the report is to be considered as containing asbestos. The 8,000 sf in the report was an estimated square footage of the roof rather than the actual square footage.
2. **Question:** If the entire work area is asbestos does the entire roof need to be double bagged?
Response: Large portions do not need to be double bagged but must be responsibly managed and lowered into the dumpster with a lift, the flashings should be double bagged. Contractor to follow all applicable health and safety regulations.
3. **Question:** If yes, is there a size limit to the bags used to remove the material off the roof?
Response: There is no size limit to the bags used to remove the ACM so long as it can be safely lowered into the dumpster and disposed of.

Include the acknowledgment of this addendum in your proposal submission.

Company Name (Print) Date

Receipt of Addendum #2: _____ (Signature)

End of Addendum #2